

数 量 総 括 表

[illegible]

舗装工			1 式当り
名称	計算式	単位	数量
舗装版撤去 t=5cm	面積計算書より A1 = 318.75 = 318.8	m ²	
アスファルト殻運搬	318.75 × 0.05 = 15.94	m ³	
アスファルト殻処分	15.94 × 2.35 = 37.4	t	
不陸整正 補足材あり M-30 t=3cm	面積計算書より A = 318.8 = 318.8	m ²	
表層工(車道舗装) 再生密粒度アスファルト(20) t=5cm	面積計算書より A1 = 318.8 = 318.8	m ²	

鋪 装 面 積 計 算 書

路線	測 点	距 離	舗装工 (表層工 t=50)				
			点間距離	幅	平均幅	面 積	備 考
	No. 0			5.90			
	No. 1	20.00	20.00	5.90	5.90	118.0	
	No. 2	40.00	20.00	5.80	5.85	117.0	
	No. 2 + 11.00	51.00	11.00	5.80	5.80	63.8	
	No. 2 + 11.00	51.00	0.00	6.60	6.20	0.0	
	No. 2 + 14.00	54.00	3.00	6.70	6.65	20.0	
	小 計					318.8	

区画線工 数量集計表

名 称		数 量 (m)								備考
		外側線 白実線 W=15cm	中央線 白実線 W=30cm	外側線 白破線 W=15cm	横断歩道 白実線 W=45cm	停止線 白実線 W=45cm	文字 白実線(換算) W=15cm	文字 黄実線(換算) W=15cm		
溶融式 区画線	1	54.0		6.3				3.0		
		54.0		6.3						
合 計		108.0	0.0	12.6	0.0	0.0	0.0	3.0		