

[illegible]

[illegible]

舗装工				1 式 当 り	
名 称	計 算 式			単 位	数 量
舗装版撤去工 t=5cm	面積計算書より A1 = 2916.4 = 2916.4			m ²	2920
不陸整正 補足材あり M-30 t=3cm	面積計算書より A1 = 2916.4 = 2916.4			m ²	2920
表層工(車道舗装) 再生密粒度アスファルト t=5cm	面積計算書より A1 = 2916.4 = 2916.4			m ²	2920

舗装版撤去工・表層工					車道舗装工			面積計算書（明和町）							
測点	距離	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	合計	摘要
ANo 0		(m)	(m)	(m ²)	(m)	(m)	(m ²)	(m)	(m)	(m ²)	(m)	(m)	(m ²)	(m ²)	
+ 0.000		5.05													
ANo 1	20.0		4.950	99.0										99.0	
+ 0.000		4.85													
ANo 2	20.0		4.900	98.0										98.0	
+ 0.000		4.95													
ANo 3	20.0		4.950	99.0										99.0	
+ 0.000		4.95													
ANo 4	20.0		5.000	100.0										100.0	
+ 0.000		5.05													
ANo 5	20.0		5.050	101.0										101.0	
+ 0.000		5.05													
ANo 6	20.0		5.050	101.0										101.0	
+ 0.000		5.05													
ANo 7	20.0		5.025	100.5										100.5	
+ 0.000		5.00													
ANo 7	17.8		5.100	90.8										90.8	
+ 17.800		5.20													
				20.0										20.0	
BNo 0														0.0	
+ 0.000		5.30													
BNo 1	20.0		5.300	106.0										106.0	
+ 0.000		5.30													
BNo 2	20.0		5.250	105.0										105.0	
+ 0.000		5.20													
BNo 3	20.0		5.200	104.0										104.0	
+ 0.000		5.20													
BNo 3	3.0		5.200	15.6										15.6	
+ 3.000		5.20													
				10.0										10.0	
小計	221			1,149.9			0.0			0.0				1,149.9	
中計				1,149.9			0.0			0.0				1,149.9	
合計				1,149.9			0.0			0.0				1,149.9	

舗装版撤去工・表層工					車道舗装工			面積計算書（明和町）							
測点	距離	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	合計	摘要
CNo 0		(m)	(m)	(m ²)	(m)	(m)	(m ²)	(m)	(m)	(m ²)	(m)	(m)	(m ²)	(m ²)	
+ 0.000		5.10													
CNo 1	20.0		5.125	102.5										102.5	
+ 0.000		5.15													
CNo 2	20.0		5.125	102.5										102.5	
+ 0.000		5.10													
CNo 3	20.0		5.150	103.0										103.0	
+ 0.000		5.20													
CNo 3	4.4		5.200	22.9										22.9	
+ 4.400		5.20													
				10.0										10.0	
DNo 0														0.0	
+ 0.000		5.15													
DNo 1	20.0		5.125	102.5										102.5	
+ 0.000		5.10													
DNo 2	20.0		5.150	103.0										103.0	
+ 0.000		5.20													
DNo 3	20.0		5.150	103.0										103.0	
+ 0.000		5.10													
DNo 3	10.4		5.100	53.0										53.0	
+ 10.400		5.10													
				10.0										10.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
小計	135			712.4			0.0			0.0				712.4	
中計				1,862.3			0.0			0.0				1,862.3	
合計				1,862.3			0.0			0.0				1,862.3	

舗装版撤去工・表層工					車道舗装工			面積計算書（明和町）							
測点	距離	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	合計	摘要
ENo 0		(m)	(m)	(m 2)	(m)	(m)	(m 2)	(m)	(m)	(m 2)	(m)	(m)	(m 2)	(m 2)	
+ 0.000		4.60													
ENo 1	20.0		4.600	92.0										92.0	
+ 0.000		4.60													
ENo 2	20.0		4.550	91.0										91.0	
+ 0.000		4.50													
ENo 3	20.0		4.550	91.0										91.0	
+ 0.000		4.60													
ENo 4	20.0		4.600	92.0										92.0	
+ 0.000		4.60													
ENo 5	20.0		4.725	94.5										94.5	
+ 0.000		4.85													
ENo 6	20.0		4.850	97.0										97.0	
+ 0.000		4.85													
ENo 6	0.4		4.850	1.9										1.9	
+ 0.400		4.85													
														0.0	
														0.0	
FNo 0															
+ 0.000		4.75													
FNo 1	20.0		4.700	94.0										94.0	
+ 0.000		4.65													
FNo 2	20.0		4.700	94.0										94.0	
+ 0.000		4.75													
FNo 3	20.0		4.750	95.0										95.0	
+ 0.000		4.75													
FNo 4	20.0		4.725	94.5										94.5	
+ 0.000		4.70													
FNo 5	20.0		4.675	93.5										93.5	
+ 0.000		4.65													
FNo 5	5.1		4.650	23.7										23.7	
+ 5.100		4.65													
小計	226			1,054.1			0.0			0.0				1,054.1	
中計				2,916.4			0.0			0.0				2,916.4	
合計				2,916.4			0.0			0.0				2,916.4	

延長調書

名 称	No.	測 点		数 量	摘 要
		自	至		
舗装版切断 t=5cm	ANo.	0	+ 0.0	5.1	
	BNo.	0	+ 16.4	5.3	
	CNo.	0	+ 0.0	5.1	
	DNo.	0	+ 0.0	5.2	
	ENo.	0	+ 0.0	4.6	
	ENo.	6	+ 0.4	4.9	
	FNo.	0	+ 0.0	4.8	
	FNo.	5	+ 5.1	4.7	
				合計	39.7