
[illegible]

舗 装 工			1 式 当 り
名 称	計 算 式	単 位	数 量
舗装版切断 アスファルト t=15cm以下	延長調書①より L= 148.10	m	150
舗装版撤去 アスファルト t=5cm	面積計算書より A= 797.09	m ²	800
不陸整正 補足材あり M-30 t=3cm	面積計算書より A= 797.09	m ²	800
表層工 再生密粒度As(13) TOP13mm t=5cm	面積計算書より A= 797.09	m ²	800
溶融式区画線 白実線 W=15cm	延長調書②より L= 208.7	m	210
溶融式区画線 白破線 W=15cm	延長調書②より L= 98.60	m	99

構 造 物 撤 去 工

延 長 調 書 ①

名 称	測 点		測 点		数 量	摘 要
			自	至		
舗装版切断 アスファルト t=15cm以下			No. 0	No. 0	5.7	
			No. 0	No. 6 + 10.30	106.7	
			No. 1 + 6.60	No. 1 + 11.60	5.0	
			No. 1 + 6.50	No. 1 + 11.50	5.0	
			No. 3 + 2.40	No. 3 + 7.40	5.0	
			No. 3 + 1.80	No. 3 + 6.80	5.0	
			No. 4 + 17.30	No. 5 + 2.30	5.0	
			No. 4 + 17.30	No. 5 + 2.30	5.0	
			No. 5 + 6.70	No. 5 + 6.70	5.7	
				合計	148.1 m	

区 画 線 工

延 長 調 書 ②

名 称	測 点		測 点		数 量	摘 要
			自	至		
溶融式区画線 白実線 W=15cm			No. 0 + 0.00	No. 1 + 4.10	29.4	
			No. 0 + 0.00	No. 1 + 3.00	28.5	
			No. 1 + 14.10	No. 2 + 19.90	36.7	
			No. 1 + 15.00	No. 2 + 18.80	34.3	
			No. 3 + 9.90	No. 4 + 14.70	35.0	
			No. 3 + 10.30	No. 4 + 13.80	33.9	
			No. 5 + 5.80	No. 5 + 6.70	5.3	
			No. 5 + 5.80	No. 5 + 6.70	5.6	
			合 計		208.7	m
溶融式区画線 白破線 W=15cm			No. 0 + 0.00	No. 6 + 10.30	65.1	
			No. 1 + 4.10	No. 1 + 14.10	5.0	
			No. 1 + 3.00	No. 1 + 15.00	6.0	
			No. 2 + 19.90	No. 3 + 9.90	5.0	
			No. 2 + 18.80	No. 3 + 10.30	6.0	
			No. 4 + 14.70	No. 5 + 5.80	5.5	
			No. 4 + 13.80	No. 5 + 5.80	6.0	
			合 計		98.6	m