

[illegible]

[illegible]

舗装工				1 式 当 り	
名 称	計 算 式			単 位	数 量
舗装版撤去工 t=5cm	面積計算書より A1 = 1372.6 = 1372.6			m ²	1370
不陸整正 補足材あり M-30 t=3cm	面積計算書より A1 = 1372.6 = 1372.6			m ²	1370
表層工(車道舗装) 再生密粒度アスファルト t=5cm	面積計算書より A1 = 1372.6 = 1372.6			m ²	1370

舗装版撤去工・表層工					車道舗装工					面積計算書（滝呂町）					
測点	距離	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	合計	摘要
No 0		(m)	(m)	(m ²)	(m)	(m)	(m ²)	(m)	(m)	(m ²)	(m)	(m)	(m ²)	(m ²)	
+ 0.000		3.90													
No 1	20.0		3.900	78.0										78.0	
+ 0.000		3.90													
No 2	20.0		3.900	78.0										78.0	
+ 0.000		3.90													
No 3	20.0		3.950	79.0										79.0	
+ 0.000		4.00													
No 4	20.0		4.050	81.0										81.0	
+ 0.000		4.10													
No 5	20.0		4.350	87.0										87.0	
+ 0.000		4.60													
No 6	20.0		4.325	86.5										86.5	
+ 0.000		4.05													
No 7	20.0		3.900	78.0										78.0	
+ 0.000		3.75													
No 8	20.0		3.600	72.0										72.0	
+ 0.000		3.45													
No 9	20.0		3.375	67.5										67.5	
+ 0.000		3.30													
No 10	20.0		3.250	65.0										65.0	
+ 0.000		3.20													
No 11	20.0		3.200	64.0										64.0	
+ 0.000		3.20													
No 12	20.0		3.300	66.0										66.0	
+ 0.000		3.40													
No 13	20.0		3.600	72.0										72.0	
+ 0.000		3.80													
No 14	20.0		3.700	74.0										74.0	
+ 0.000		3.60													
No 15	20.0		3.450	69.0										69.0	
+ 0.000		3.30													
小計	300			1,117.0			0.0			0.0				1,117.0	
中計				1,117.0			0.0			0.0				1,117.0	
合計				1,117.0			0.0			0.0				1,117.0	

面積計算書（滝呂町）															
舗装版撤去工・表層工					車道舗装工										
測点	距離	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	合計	摘要
		(m)	(m)	(m ²)	(m)	(m)	(m ²)	(m)	(m)	(m ²)	(m)	(m)	(m ²)	(m ²)	
No 15															
+ 0.000		3.30													
No 16	20.0		3.225	64.5										64.5	
+ 0.000		3.15													
No 17	20.0	3.30	3.225	64.5										64.5	
+ 0.000		4.70													
No 17	12.0		3.650	43.8										43.8	
+ 12.000		2.60													
No 18	8.0		3.200	25.6										25.6	
+ 0.000		3.80													
No 18	9.0		6.350	57.2										57.2	
+ 9.000		8.90													
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
小計	69			255.6			0.0			0.0				255.6	
中計				1,372.6			0.0			0.0				1,372.6	
合計				1,372.6			0.0			0.0				1,372.6	

延長調書

名 称	No.	測 点		数 量	摘 要
		自	至		
舗装版切断 t=5cm	No.	0	+ 0.0	3.9	
	No.	0	+ 0.0	18 + 9.0	738.0
	No.	18	+ 9.0	8.9	

[illegible]

区 画 線 集 計 表

区画線

単位:m

名 称	規 格	施 工 区 分	適 用	数 量	
				その他の 舗装区間	排水性 舗装区間
溶融式区画線	白 実線 W=15cm	供用区間		349.0	
		計		349.0	
	白 破線 W=15cm	供用区間		190.0	
		計		190.0	

区画線工

(1 / 1)

延長調書

[illegible]