

## 数 量 総 括 表

[illegible]

# 鋪 装 面 積 計 算 書

路線	測 点		距 離	舗装工 ( 表層工 t=50 )				
				点間距離	幅	平均幅	面 積	備 考
	No.	0			3.80			
	No.	1	20.00	20.00	3.80	3.80	76.0	
	No.	2	40.00	20.00	3.80	3.80	76.0	
	No.	2 + 14.10	54.10	14.10	3.80	3.80	53.6	
	No.	2 + 14.10	54.10	0.00	4.20	4.00	0.0	
	No.	3	60.00	5.90	4.20	4.20	24.8	
	No.	3 + 19.60	79.60	19.60	4.20	4.20	82.3	
	No.	3 + 19.60	79.60	(0.00)	3.80	4.00	0.0	
	No.	4	80.00	0.40	3.80	3.80	1.5	
	No.	5	100.00	20.00	3.80	3.80	76.0	
	No.	6	120.00	20.00	3.80	3.80	76.0	
	No.	6 + 14.20	134.20		3.80	3.80	0.0	
	No.	6 + 14.20	134.20	(0.00)	4.20	4.00	0.0	
	No.	7	140.00	5.80	4.20	4.20	24.4	
	No.	8	160.00	20.00	4.20	4.20	84.0	
	No.	9	180.00	20.00	4.20	4.20	84.0	
	No.	9 + 7.40	187.40	7.40	4.20	4.20	31.1	
	No.	9 + 7.40	187.40	0.00	3.80	4.00	0.0	
	No.	10	200.00	12.60	3.80	3.80	47.9	
	No.	10 + 14.00	214.00	14.00	3.80	3.80	53.2	
	合 計						790.7	

区画線工 数量集計表

名 称		数 量 (m)								備考
		外側線 白実線 W=15cm	中央線 白実線 W=30cm	外側線 白破線 W=15cm	横断歩道 白実線 W=45cm	停止線 白実線 W=45cm	文字 白実線(換算) W=15cm			
溶融式 区画線	1	214.0					34.0			
合 計		214.0	0.0	0.0	0.0	0.0	34.0			