

[illegible]

[illegible]

舗装工				1 式当り	
名称	計算式			単位	数量
舗装版撤去工 t=5cm	面積計算書より A1= 3151.4 = 3151.4			m ²	3150
不陸整正 補足材あり M-30 t=5cm	面積計算書より A1= 3151.4 = 3151.4			m ²	3150
表層工(車道舗装) 再生密粒度アスファルト t=5cm	面積計算書より A1= 3151.4 = 3151.4			m ²	3150

構造物撤去工

(1 / 1)

延長調書

名 称	No.	測 点		数 量	摘 要
		自	至		
舗装版切断 t=5cm	A No.	0 + 0.0		5.4	
	A No.	4 + 10.0	5 + 0.0	20.0	
	A No.	9 + 14.5		5.2	
	B No.	0 + 0.0		5.5	
	B No.	4 + 10.0	5 + 0.0	20.0	
	B No.	10 + 2.5		5.2	
	C No.	0 + 0.0		3.8	
	C No.	4 + 10.0	5 + 0.0	10.0	
	C No.	10 + 8.5		3.8	
	C No.	0 + 0.0	10 + 8.8	208.5	
	C No.	1 + 9.0		3.6	
	C No.	2 + 5.0		3.6	
	C No.	2 + 8.0		3.6	
	C No.	2 + 15.0		3.6	
	C No.	2 + 18.0		3.6	
	C No.	3 + 4.0		3.6	
	C No.	3 + 7.0		3.6	
	C No.	4 + 4.0		3.6	
	C No.	4 + 7.0		3.6	
	C No.	5 + 15.0		3.6	
	C No.	5 + 18.0		3.6	
	C No.	6 + 17.0		3.6	
	C No.	7 + 0.0		3.6	
	C No.	8 + 17.0		3.6	
	C No.	9 + 0.0		3.6	
	C No.	9 + 9.0		3.6	
	C No.	9 + 12.0		3.6	
			合計	348.6	

面積計算書（滝呂町）															
舗装版撤去工・表層工					車道舗装工										
測点	距離	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	合計	摘要
ANo 0		(m)	(m)	(m 2)	(m)	(m)	(m 2)	(m)	(m)	(m 2)	(m)	(m)	(m 2)	(m 2)	
+ 0.000		5.35													
ANo 1	20.0		5.350	107.0										107.0	
+ 0.000		5.35													
ANo 2	20.0		5.325	106.5										106.5	
+ 0.000		5.30													
ANo 3	20.0		5.350	107.0										107.0	
+ 0.000		5.40													
ANo 4	20.0		5.425	108.5										108.5	
+ 0.000		5.45													
ANo 5	20.0		5.575	111.5										111.5	
+ 0.000		5.70													
ANo 6	20.0		5.500	110.0										110.0	
+ 0.000		5.30													
ANo 7	20.0		5.375	107.5										107.5	
+ 0.000		5.45													
ANo 8	20.0		5.450	109.0										109.0	
+ 0.000		5.45													
ANo 9	20.0		5.450	109.0										109.0	
+ 0.000		5.45													
ANo 9	14.5		5.300	76.9										76.9	
+ 14.500		5.15													
				125.0										125.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
小計	195			1,177.9			0.0			0.0				1,177.9	
中計				1,177.9			0.0			0.0				1,177.9	
合計				1,177.9			0.0			0.0				1,177.9	

舗装版撤去工・表層工					車道舗装工			面積計算書（滝呂町）							
測点	距離	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	合計	摘要
BNo 0		(m)	(m)	(m ²)	(m)	(m)	(m ²)	(m)	(m)	(m ²)	(m)	(m)	(m ²)	(m ²)	
+ 0.000		5.50													
BNo 1	20.0		5.500	110.0										110.0	
+ 0.000		5.50													
BNo 2	20.0		5.450	109.0										109.0	
+ 0.000		5.40													
BNo 3	20.0		5.400	108.0										108.0	
+ 0.000		5.40													
BNo 4	20.0		5.400	108.0										108.0	
+ 0.000		5.40													
BNo 5	20.0		5.425	108.5										108.5	
+ 0.000		5.45													
BNo 6	20.0		5.425	108.5										108.5	
+ 0.000		5.40													
BNo 7	20.0		5.350	107.0										107.0	
+ 0.000		5.30													
BNo 8	20.0		5.350	107.0										107.0	
+ 0.000		5.40													
BNo 9	20.0		5.300	106.0										106.0	
+ 0.000		5.20													
BNo 10	20.0		5.200	104.0										104.0	
+ 0.000		5.20													
BNo 10	2.5		5.200	13.0										13.0	
+ 2.500		5.20													
														0.0	
														0.0	
														0.0	
														0.0	
小計	203			1,089.0			0.0			0.0				1,089.0	
中計				2,266.9			0.0			0.0				2,266.9	
合計				2,266.9			0.0			0.0				2,266.9	

舗装版撤去工・表層工					車道舗装工			面積計算書（滝呂町）							
測点	距離	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	合計	摘要
CNo 0		(m)	(m)	(m ²)	(m)	(m)	(m ²)	(m)	(m)	(m ²)	(m)	(m)	(m ²)	(m ²)	
+ 0.000		3.80													
CNo 1	20.0		3.800	76.0										76.0	
+ 0.000		3.80													
CNo 2	20.0		3.800	76.0										76.0	
+ 0.000		3.80													
CNo 3	20.0		3.775	75.5										75.5	
+ 0.000		3.75													
CNo 4	20.0		3.750	75.0										75.0	
+ 0.000		3.75													
CNo 5	20.0		3.625	72.5										72.5	
+ 0.000		3.50													
CNo 6	20.0		3.675	73.5										73.5	
+ 0.000		3.85													
CNo 7	20.0		3.825	76.5										76.5	
+ 0.000		3.80													
CNo 8	20.0		3.825	76.5										76.5	
+ 0.000		3.85													
CNo 9	20.0		3.850	77.0										77.0	
+ 0.000		3.85													
CNo 10	20.0		3.825	76.5										76.5	
+ 0.000		3.80													
CNo 10	8.5		3.800	32.3										32.3	
+ 8.500		3.80													
														0.0	
														0.0	
														0.0	
														0.0	
小計	209			787.3			0.0			0.0				787.3	
中計				3,054.2			0.0			0.0				3,054.2	
合計				3,054.2			0.0			0.0				3,054.2	

舗装版撤去工・表層工					車道舗装工			面積計算書（滝呂町）							
測点	距離	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	合計	摘要
CNo 1		(m)	(m)	(m ²)	(m)	(m)	(m ²)	(m)	(m)	(m ²)	(m)	(m)	(m ²)	(m ²)	
+ 9.000		3.60													
CNo 1	3.0		3.600	10.8										10.8	
+ 12.000		3.60													
CNo 2														0.0	
+ 5.000		3.60													
CNo 2	3.0		3.600	10.8										10.8	
+ 8.000		3.60													
CNo 2														0.0	
+ 15.000		3.60													
CNo 2	3.0		3.600	10.8										10.8	
+ 18.000		3.60													
CNo 3														0.0	
+ 4.000		3.60													
CNo 3	3.0		3.600	10.8										10.8	
+ 7.000		3.60													
CNo 4														0.0	
+ 4.000		3.60													
CNo 4	3.0		3.600	10.8										10.8	
+ 7.000		3.60													
CNo 5														0.0	
+ 15.000		3.60													
CNo 5	3.0		3.600	10.8										10.8	
+ 18.000		3.60													
CNo 6														0.0	
+ 17.000		3.60													
CNo 7	3.0		3.600	10.8										10.8	
+ 0.000		3.60													
CNo 8	37.0													0.0	
+ 17.000		3.60													
CNo 9	3.0		3.600	10.8										10.8	
+ 0.000		3.60													
小計	61			86.4			0.0			0.0				86.4	
中計				3,140.6			0.0			0.0				3,140.6	
合計				3,140.6			0.0			0.0				3,140.6	

舗装版撤去工・表層工					車道舗装工			面積計算書（滝呂町）							
測点	距離	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	合計	摘要
CNo 9		(m)	(m)	(m 2)	(m)	(m)	(m 2)	(m)	(m)	(m 2)	(m)	(m)	(m 2)	(m 2)	
+ 9.000		3.60													
CNo 9	3.0		3.600	10.8										10.8	
+ 12.000		3.60													
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
小計	3			10.8			0.0			0.0				10.8	
中計				3,151.4			0.0			0.0				3,151.4	
合計				3,151.4			0.0			0.0				3,151.4	