

[illegible]

[illegible]

舗装工				1 式 当 り	
名 称	計 算 式			単 位	数 量
舗装版撤去工 t=5cm	面積計算書より A1 = 2449.9 = 2449.9			m ²	2450
不陸整正 補足材あり M-30 t=5cm	面積計算書より A1 = 2449.9 = 2449.9			m ²	2450
表層工(車道舗装) 再生密粒度アスファルト t=5cm	面積計算書より A1 = 2449.9 = 2449.9			m ²	2450

舗装版撤去工・表層工					車道舗装工			面積計算書（明和町）							
測点	距離	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	合計	摘要
ANo 0		(m)	(m)	(m 2)	(m)	(m)	(m 2)	(m)	(m)	(m 2)	(m)	(m)	(m 2)	(m 2)	
+ 0.000		5.00													
ANo 1	20.0		5.000	100.0										100.0	
+ 0.000		5.00													
ANo 2	20.0		4.950	99.0										99.0	
+ 0.000		4.90													
ANo 2	11.0		4.900	53.9										53.9	
+ 11.000		4.90													
														0.0	
														0.0	
BNo 0			2.750	0.0											
+ 0.000		5.50													
BNo 1	20.0		5.500	110.0										110.0	
+ 0.000		5.50													
BNo 2	20.0		5.500	110.0										110.0	
+ 0.000		5.50													
BNo 3	20.0		5.500	110.0										110.0	
+ 0.000		5.50													
BNo 3	9.0		5.500	49.5										49.5	
+ 9.000		5.50													
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
小計	120			632.4			0.0			0.0				632.4	
中計				632.4			0.0			0.0				632.4	
合計				632.4			0.0			0.0				632.4	

舗装版撤去工・表層工					車道舗装工			面積計算書（明和町）							
測点	距離	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	合計	摘要
CNo 0		(m)	(m)	(m ²)	(m)	(m)	(m ²)	(m)	(m)	(m ²)	(m)	(m)	(m ²)	(m ²)	
+ 0.000		5.00													
CNo 1	20.0		5.000	100.0										100.0	
+ 0.000		5.00													
CNo 2	20.0		5.000	100.0										100.0	
+ 0.000		5.00													
CNo 3	20.0		5.050	101.0										101.0	
+ 0.000		5.10													
CNo 4	20.0		5.050	101.0										101.0	
+ 0.000		5.00													
CNo 5	20.0		5.550	111.0										111.0	
+ 0.000		6.10													
CNo 6	20.0		6.100	122.0										122.0	
+ 0.000		6.10													
CNo 7	20.0		6.150	123.0										123.0	
+ 0.000		6.20													
CNo 8	20.0		6.075	121.5										121.5	
+ 0.000		5.95													
CNo 9	20.0		5.950	119.0										119.0	
+ 0.000		5.95													
CNo 10	20.0		6.025	120.5										120.5	
+ 0.000		6.10													
CNo 11	20.0		6.100	122.0										122.0	
+ 0.000		6.10													
CNo 11	14.5		6.100	88.5										88.5	
+ 14.500		6.10													
														0.0	
														0.0	
														0.0	
小計	235			1,329.5			0.0			0.0				1,329.5	
中計				1,961.9			0.0			0.0				1,961.9	
合計				1,961.9			0.0			0.0				1,961.9	

面積計算書（明和町）															
舗装版撤去工・表層工					車道舗装工										
測点	距離	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	幅員	平均幅員	面 積	合計	摘要
DNo 0		(m)	(m)	(m 2)	(m)	(m)	(m 2)	(m)	(m)	(m 2)	(m)	(m)	(m 2)	(m 2)	
+ 0.000		5.00													
DNo 1	20.0		5.000	100.0										100.0	
+ 0.000		5.00													
DNo 2	20.0		4.950	99.0										99.0	
+ 0.000		4.90													
DNo 3	20.0		4.875	97.5										97.5	
+ 0.000		4.85													
DNo 4	20.0		5.175	103.5										103.5	
+ 0.000		5.50													
DNo 4	16.0		5.500	88.0										88.0	
+ 16.000		5.50													
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
														0.0	
小計	96			488.0			0.0			0.0				488.0	
中計				2,449.9			0.0			0.0				2,449.9	
合計				2,449.9			0.0			0.0				2,449.9	

延長調書

名 称	No.	測 点		数 量	摘 要
		自	至		
舗装版切断 t=5cm	ANo.	2	+ 11.0	4.9	
	BNo.	0	+ 0.0	5.5	
	BNo.	3	+ 9.0	5.5	
	CNo.	11	+ 14.5	6.1	
	DNo.	4	+ 16.0	5.5	
</					